

Bare Space – Rules and regulations for stall decor

- Marked floor space will be given as per the final layout
- For single level stands, the max height of the wall paneling should be 2.5mtrs from the floor level and the maximum height for any branding should be within 3.5 mtrs
- Bare space exhibitors are requested to share with the organizers, the details of their respective stall decoration contractors.
- Bare space exhibitors should submit their final designs to the organisers for approval from their technical team a minimum of 10 days before start of work at site.
- Exhibitors are requested to get the service badges from the organizers and to issue the same to their respective stall decoration contractors.
- People without badges will not be allowed into the halls during the set-up and event period.
- Wood Cutting, spray painting & Welding works are not permitted inside the hall.
- Temporary power can be drawn from the nearest DB as indicated by the official infrastructure providers during set-up period.
- Permanent power as per requirement will be given by the official infrastructure provider @ an additional cost up to one corner of the stall. Internal wiring for the still should be done and maintained by your stand contractor
- The exhibitors are advised to engage certified ('B' certificate) electrical contractors for their electrical work and to use quality wires / cables .
- The agencies are strictly advised not to encroach / touch/use the built-up booths for working/storing of the décor and display materials.
- The stand contractors should work within the designated floor space of their respective booths & should not use the pathway/adjoining stalls for working. The pathway should be completely cleared for laying of carpets on **20.09.23** evening @ **8.00 PM**. Any materials found lying on the pathways will be removed from site by our housekeeping personnel and the organizers cannot be held responsible for any damage or loss of these materials.
- The exposed area of the booth (back / side wall) facing the pathway or the other booth should be masked completely.
- The pathways should not be encroached upon.
- Smoking / Spitting / Drinking is strictly prohibited inside the halls.
- The stand contractors should clear all their material from anywhere the hall/premises before the commencement of the show and remove off all the materials after the completion of the show.

Additional rules for stands with Mezzanine Floor

- Any mezzanine construction should have the drawing clearance and stability certificate from a chartered structural engineer and the same has to be submitted along with the stall drawings, to the organisers, 10 days before the commencement of work at site.
- The mezzanine should be at a height on maximum 3.00mtrs from the natural floor level of the hall. The maximum height of any construction / branding on the mezzanine level should be within 4 meters from the floor level of the hall.