

## **Built-up Stall Details**

### **PREFAB STALLS**

Prefab stalls as per layout using prefab system – Aluminium extrusions of powder coated vertical pillars and horizontal channels with panels using locking device.

### **PANELS**

Using white color polycom laminated panels of **1mtr** width and **2.5mtr height** and fixing powder coated vertical pillars on the sides and horizontal channels at the top and bottom.

### **NAMEBOARD**

Using color laminated board and fixing in between 2 Nos of horizontal channels at the fascia. Names – Preparing the participant's names using white vinyl and fixing on the name board.

### **ELECTRICALS**

3 nos spotlights and 1 no 5 amp power socket will be provided for every 9 sqm stall.

### **FURNITURE**

1 no. table using octonorm system with 12mm laminated top, front and sides, 2 nos chairs and 1 wastepaper bin will be provided for every 9 sqm stall.

### **EXTRA ACCESSORIES**

Additional furniture & electrical items as per catalogue can be booked in advance with the official stand contractor, through email. Advance online booking will be available till **14th July, 2023**. Post that, furniture requirements (subject to availability) can be booked at the service counter on site.

- a. Drilling / nailing / pasting with adhesives on the stall partition and channels is not permitted. Only double sided foam tapes will be permitted for fixing the display posters on the walls panels.
- b. The cost for any damage caused to the partitions, furniture, electrical, carpet etc. inside the stall will have to be paid by the exhibitor.
- c. In case of any assistance, please contact the service counter of the official stand contractor.
- d. Additional furniture & electrical items ordered @ site in the counter will be delivered within 8 hours from the time of order / receipt of the payment.

***Credit & Debit Card / UPI facility available on site to facilitate cashless transactions.***